



DOWNLIGHT TRIM MODEL: ICRY3 / 6 / 9 T - AT - 120 / UNV

IMPORTANT - READ CAREFULLY BEFORE INSTALLING FIXTURE. RETAIN THESE INSTRUCTIONS FOR FUTURE REFERENCE. THIS PRODUCT MUST BE INSTALLED IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE AND ALL APPLICABLE LOCAL CODES, BY A PERSON FAMILIAR WITH THE CONSTRUCTION AND OPERATION OF THE PRODUCT, AND THE HAZARDS INVOLVED. PROPER GROUNDING IS REQUIRED FOR SAFETY.

AIRTIGHT HOUSING INSTALLATION (AT) INTEGRAL DRIVER (120V / 120-277V) DIMMING 0-10V (D10) - TRIAC / ELV (LTE) - DALI (DA)

- A- REMOVE THE (4) PHILLIPS SCREWS IN ORDER TO OPEN THE HOUSING.
- B- REMOVE THE KNOCKOUT PLUG, INSTALL AN AIRTIGHT CONDUIT (**NOT INCLUDED**). AND A CONDUIT CONNECTOR (**NOT INCLUDED**).
*0-10V DIMMING: REMOVE AN EXTRA KNOCKOUT PLUG, INSTALL AN AIR TIGHT CONDUIT AND A CONDUIT CONNECTOR (**NOT INCLUDED**).
- C- CLOSE THE HOUSING BY SCREWING THE (4) PHILLIPS SCREWS PREVIOUSLY REMOVED (A). LEAVE AT LEAST 6" (152mm) OF FEEDER CABLE ACCESSIBLE FROM UNDER THE CEILING.
- D- ENGAGE (4) HANGER BARS IN HOUSING SLOTS AVAILABLE AND CONNECT THEM TOGETHER.




DOWNLIGHT TRIM MODEL: ICRY3 / 6 / 9 T - AT - 120 / UNV


E- FASTEN HANGER BARS TO CEILING BRACE WITH #8 SCREWS (**NOT INCLUDED**). HOUSING MUST BE FLUSH WITH THE BOTTOM OF THE CEILING BRACES.

F- INSTALL THE DRYWALL AND MAKE THE CUT-OUT OPENING (**SEE DIMENSIONS BELOW**).

E




F




Model	Housing	Cut-out dimensions (A x B)	Ceiling thickness	Clearance
ICRY3	BI-CRY3T-AT	2 ⁹ / ₁₆ " x 7 ⁷ / ₁₆ " (64.5 x 185mm)		
ICRY6	BI-CRY6T-AT	2 ⁷ / ₁₆ " x 14 ⁵ / ₁₆ " (64.5 x 363mm)	1/8"-1 1/8" (3-29mm)	3 5/8" (92mm)
ICRY9	BI-CRY9T-AT	2 ⁷ / ₁₆ " x 21 ³ / ₁₆ " (64.5 x 543mm)		

CONNECTIONS

MAKE ALL NECESSARY CONNECTIONS (SEE WIRING DIAGRAM BELOW) USING TWIST CONNECTOR (NOT INCLUDED).



WIRING DIAGRAM



FIXTURE INSTALLATION

- A- INSERT THE LED DRIVER INSIDE THE INSULATION BOX.
- B- HOLD THE (2) CLIPS UPWARD AND INSERT FIXTURE INTO CUT-OUT.

A + B

